Megger.

High-voltage test system HPG 50-D - 80-D Compact and powerful AC and DC test systems



- Compact, maintenance free, cast-resin high-voltage transformers
- Separate control and HV units
- Continuously adjustable voltage
- A powerful system: continuous operation at 1.2 kVA; 60 min. short operation at up to 3 kVA
- DC testing via the voltage-doubler rectifying attachment

DESCRIPTION

The high voltage test sets HPG 50-D and 80-D are suitable for 50/ 60 Hz AC testing (35 to 58 kV_{RMS}) and DC testing up to 100 kV and 160 kV respectively. The DC voltage is generated via a voltage doubler. The high-voltage test systems consist of two separate units: the control unit and the high-voltage unit. This separation enables the operator to use the test set on-site without any complications.

Typical application areas:

- Testing witchgears
- Testing voltage and current transformers
- Testing MV plants/components
- DC cable testing

The two piece design allows the operator to use the unit at a safe distance. The control unit is used to operate the high voltage transformer. The control unit consists of a variac, current/ voltage display instruments, a timer for the test duration and a safety circuit. The low voltage winding can be continuously excited from zero to the maximum value so that a certain output is available for a pre-determined period. The operating duration depends on the application, ranging from a few minutes to continuous operation.

All HPG xx-D test systems at a glance:

- HPG 50-D, testing up to 35 kV_{RMS} / DC-testing up to 100 kV
- HPG 80-D, AC testing up to 58 kV_{RMS} / DC-testing up to 160 kV

TECHNICAL DATA*

	HPG 50-D		HPG 80-D
Power consumption P _N	1.2 kVA		1.2 kVA
Power consumption short-time P _k (1h)	3 kVA		2.5 kVA
Input voltage		230 V / 50 60 Hz	
Output voltage	0 35 kV _{rms} AC		0 58 kV _{rms} AC
	0 100 kV DC		0 160 kV DC
Measuring range	0 40 kV AC		0 60 kV AC
	0 100 kV DC		0 160 kV DC
Precision		1.5 %	
Output current		0 15mA	
		50 mA (1 hour)	
Measuring range	0 500 μA / 0 50 mA		
Precision		1.5 %	
Control unit HSW 3-2			
Weight		26 kg	
Dimensions (W x H x D)		520 x 255 x 320 mm	
Transformer			
Weight	94 kg		124 kg
Dimensions (W x H x D)	900 x 1065 x 450 r	nm	1000 x 1065 x 490 mm

FEATURES

- Continuous testing with AC voltages up to 1.5 kVA
- Separate control and HV-unit
- In-built over-current protection
- DC-testing via voltage doubler rectifier attachment

ORDERING INFORMATION

Product	Order no.
HPG 50-D	813219
Control unit (HSW 3-2), HV-transformer 35 kVrms, set of cables, rectifier attachment (voltage doubler), dis	charge and earthing rod 100 kV
HPG 80-D	813223
Control unit (HSW 3-2), HV-transformer 58 kV _{rms} , set of cables, rectifier attachment (voltage doubler), dis	charge and earthing rod 150 kV
Options:	
HV-connection cable 3 m (unshielded)	2005029
HV-connection cable 5 m (unshielded)	2004993
HV-connection cable 10 m (unshielded)	2005030
HV-connection cable 5 m (shielded)	810003736
HV-connection cable 10 m (shielded)	820023906

* We reserve the right to make technical changes.

SALES OFFICES

Megger GmbH

Obere Zeil 2 D-61440 Oberursel Germany T 0049 6171 92987-0 E info@megger.de Seba Dynatronic Mess- und Ortungstechnik GmbH Dr.-Herbert-lann-Str. 6 96148 Baunach Germany T 0049 9544 68-0 E team.international@megger.de

HPG50D-HPG80D_DS_EN_V01

www.megger.com ISO 9001



The word 'Megger' is a registered trademark.